




PLAN - TOP OF COVER
(TRAFFIC SIDE)



PLAN - BOTTOM OF COVER
(SOFFIT / UNDERSIDE)



SECTION THRU FRAME



PLAN - TOP OF FRAME

BUREAU OF ENGINEERING

DEPARTMENT OF PUBLIC WORKS

CITY OF LOS ANGELES


MAINTENANCE HOLE FRAME AND COVER 30-INCH

**STANDARD PLAN
S-283-3**


PREPARED
JONATHAN DE LEON
BUREAU OF ENGINEERING
CHECKED
RAFFI A. MASSABKI, P.E.
BUREAU OF ENGINEERING

SUBMITTED
Samara Ali-Ahmad 6/16/11
SAMARA ALI-AHMAD, P.E. DATE
ENGINEER OF DESIGN
Kenneth R. Redd 6/16/11
KENNETH R. REDD, P.E. DATE
DEPUTY CITY ENGINEER


APPROVED
Gary Lee Moore 6-16-11
GARY LEE MOORE, P.E. DATE
CITY ENGINEER




SUPERSEDES	REFERENCES
B-4119	S - 601
VAULT INDEX NUMBER B - 4665	
SHEET 1 OF 3 SHEETS	




SECTION "A" COVER




DETAIL OF FRAME



DETAIL C



DETAIL A - CROSS RIB



DETAIL B



NOTES

GENERAL

1. MAINTENANCE HOLE FRAME AND COVER SHALL CONFORM TO THE STANDARD SPECIFICATIONS, BROWN BOOK AND THE CITY OF LOS ANGELES STANDARD PLAN S-601 LATEST EDITION. IN CASE OF A CONFLICT BETWEEN THIS STANDARD PLAN "S-283-3" AND OTHER CITY OF LOS ANGELES STANDARD PLANS INCLUDING BUT NOT LIMITED TO STANDARD PLAN "S-601" LATEST EDITION, THIS STANDARD PLAN "S-283-3" SHALL GOVERN.
2. MAINTENANCE HOLE FRAME AND COVER SHALL BE CAST IRON CONFORMING TO SECTION 206-3 OF THE STANDARD SPECIFICATIONS AND SHALL RECEIVE AN ASPHALTIC COATING, AFTER FABRICATION EXCEPT MACHINED SURFACES, CONFORMING TO SECTION 206-3.6 OF THE STANDARD SPECIFICATIONS.
3. ALL HOLES IN CAST IRON SHALL BE DRILLED AFTER CASTING OR PLUGGED PRIOR TO CASTING. THEY SHALL NOT BE PUNCHED.
4. WEIGHT OF MAINTENANCE HOLE FRAME AND COVER SHALL BE PER THE FOLLOWING TABLE :

WEIGHT RANGE	MINIMUM	MAXIMUM
FRAME	305 LBS	335 LBS
COVER	305 LBS	335 LBS

TESTING

5. MAINTENANCE HOLE FRAME AND COVER SHALL BE TESTED FOR ACCURATE FIT, AND MARKED IN SETS PRIOR TO DELIVERY TO THE JOB SITE.
6. MAINTENANCE HOLE FRAME AND COVER SHALL BE TESTED FOR STRUCTURAL AND IMPACT LOADING, DEFLECTION, LONG TERM ABRASION AND SLIP RESISTANCE IN ACCORDANCE WITH THE CITY OF LOS ANGELES STANDARD PLAN S-601, LATEST EDITION.
7. PROVIDE FABRICATION / BATCH INSPECTION PER SUBSECTION 206-3.2 OF THE STANDARD SPECIFICATION. THE PROOF-LOAD FOR TEST METHOD B, SUBSECTION 206-3.2 OF THE STANDARD SPECIFICATION IS 52,000 LBS.

MARKINGS

8. MAINTENANCE HOLE COVERS FOR USE ON SEWER STRUCTURES SHALL BEAR THE LETTER "S" AND ON STORM DRAIN STRUCTURES THE LETTER "D" LOCATED AT THE CENTER OF THE COVER. SEE DETAIL B ON SHEET 2.
9. MARKINGS LOCATED ON FRAME AND TOP OF COVER SHALL BE FLUSH WITH FINISHED SURFACE. MARKINGS LOCATED ON THE COVER SOFFIT SHALL BE RAISED ABOVE THE ADJACENT FINISHED SURFACE. ETCHING, DIE STAMPING, ENGRAVING OR WELDING ON MARKINGS WILL NOT BE ACCEPTED.
10. COVER TYPE, IDENTIFICATION, FOUNDRY, HEAT NUMBER, MANUFACTURING DATE AND THE ENGLISH NAME OF COUNTRY OF ORIGIN PRECEDED BY "MADE IN" MARKINGS SHALL BE PER THE FOLLOWING TABLE. ALL MARKINGS SHALL BE RAISED, FLAT FACE LETTERS MARKED BY MEANS OF CAST-IN-MOLD LETTERING.

COVER		MARKINGS	FRAME
TOP SURFACE (Traffic side)	BOTTOM SURFACE (Soffit/ Underside)	DESCRIPTION, LOCATION AND SIZE * (Height x Line Width x Depth)	INNER BASE (Exposed side)
IDENTIFICATION			
1-1/2" X 1/4" X 3/16"		" PRIVATE " or " CITY OF LOS ANGELES "	5/16" X 3/16" X 3/16"
COUNTRY OF ORIGIN			
1-1/2" X 1/4" X 3/16"		MADE IN " THE ENGLISH NAME OF COUNTRY OF ORIGIN "	5/16" X 3/16" X 3/16"
TYPE of MAINTENANCE HOLE			
Height X 1/4" X 3/16" (See Detail B)		" S " for Sewer MH " D " for Storm Drain MH	
OTHER			
	5/16" X 3/16" X 3/16"	FOUNDRY NAME MANUFACTURING DATE and/ HEAT NUMBER	5/16" X 3/16" X 3/16"

* Adjust spacing, kerning and/or mortising of letters as needed such that letters appear evenly spaced. The minimum spacing between words shall be 1/2 of the letter height specified.

