



**NOTES:**

1. ALL REINFORCING SHALL BE NO. 4 BARS AT 12" O.C. BOTH WAYS IN TOP SLAB AND WALLS
2. CATCH BASIN SHALL BE CONSTRUCTED OF 560-C-3250 CONCRETE.
3. CURB AND GUTTER ADJOINING CATCH BASIN SHALL BE CONSTRUCTED PRIOR TO CONSTRUCTING TOP OF CATCH BASIN. (50' EACH WAY)

CITY OF CHINO HILLS	<p style="font-size: 1.2em; margin: 0;">TYPE "A"</p> <p style="font-size: 1.2em; margin: 0;">CATCH BASIN</p>	205
	<p style="font-size: 1.2em; margin: 0;"><i>CHRIS VOGT</i></p> <p style="font-size: 0.8em; margin: 0;">CITY ENGINEER</p>	