



**NOTES**

1. IN CASES WHERE THE CONTRACTOR IS UNABLE TO PLACE THE MONUMENT, SUCH AS CONFLICTS WITH UNDERGROUND UTILITIES, THE CONTRACTOR SHALL NOTIFY THE ENGINEER FOR REVIEW, CONFIRMATION, AND APPROVAL OF THE OMISSION.
2. NOTIFY U.S.A. TO MARK UTILITIES 48 HOURS PRIOR TO EXCAVATION.
3. PAVEMENT SHALL BE CORE-DRILLED WITH AN 18"  $\phi$  DIAMOND BIT. JACK HAMMERING OF PAVEMENT WILL NOT BE PERMITTED.
4. 4"  $\phi$  DOMED CONCRETE MARKER (BERNTSEN C&D), 8"  $\phi$  GALVANIZED SLEEVE, 8"  $\phi$  SCH. 40 PVC PIPE AND 10"  $\phi$  MONUMENT COVER WILL BE SUPPLIED BY THE CONTRACTOR.
5. 4"  $\phi$  DOMED CONCRETE MARKER SHALL BE SET/ADJUSTED WITH A TOLERANCE OF  $\pm 1/2$ " OF THE CENTERLINE POINT.
6. SURVEY WELL MONUMENT COVERS SHALL BE ADJUSTED FLUSH TO NEW FINISHED PAVEMENT SURFACE. REPLACE GALVANIZED SLEEVE WHEN NEEDED.
7. CITY OF GLENDALE SURVEY SECTION SHALL BE NOTIFIED FIVE (5) WORKING DAYS PRIOR TO CONTRACTOR INSTALLING OR ADJUSTING SURVEY WELL MONUMENT.
8. AFTER CONTRACTOR HAS INSTALLED SURVEY WELL MONUMENT, CITY OF GLENDALE SURVEY SECTION SHALL CHISEL PUNCH THE DOMED CONCRETE MARKER.

REVISIONS			PUBLIC WORKS DEPARTMENT, ENGINEERING DIVISION CITY OF GLENDALE, CALIFORNIA			
BY	DATE	DESCRIPTION	<b>SURVEY WELL MONUMENT</b> SUBMITTED: _____ APPROVED: _____ STANDARD PLAN <b>25-154</b>			
RDC	11/03	DESIGN & NOTED (CONTRACTING)				
RJR	11/04	OWNER & NOTES (CONTRACTING)				
RJR	02/05	DESIGN & NOTES				
RJR	02/06	NEW DESIGN				