



X-SECTION

ALTER. X-SECTION

INVERT PLAN

NOTES:

1. Height of Shaft Pipe and Riser Rings to be made of Standard Units.
2. All Units Reinforced Single Cage:
3. R. C. P. Shall be Min. D 1000.
4. Mortar shall be 1 Cement to two Sand.
5. Contractor Shall Form and Pour Concrete Base with Cover Adjusted as Shown. After Final Paving Operation Entire Dirt Excavation for Frame Adjustment to be Backfilled with Concrete.

Portland Cement Concrete Base of 5 sack mix.

CONCRETE BASE ADD'N SEE NOTE 5		9-22-60	DWB
REVISIONS		DATE	APPR. BY
CITY OF COLTON PUBLIC WORKS DEPT.			
STANDARD R.C.P. MANHOLE			
DRAWN BY	G.W.A.	SCALE	N.T.S.
CHK'D		DATE	AUGUST 1963
APP'D	<i>L. Glenn Wilson</i>		301