



**NOTES:**

1. NO CLEAN-OUT SHALL BE PLACED IN FRONT OF DRIVEWAYS EXCEPT ON CUL-DE-SACS.
2. CONCRETE SHALL CONTAIN NOT LESS THAN 550 POUNDS OF CEMENTITIOUS MATERIAL PER CUBIC YARD WITH 4% AIR ENTRAINMENT.
3. FINISH GRADE STAKE SHALL BE SET AT EACH CLEAN-OUT TO CONFIRM MAXIMUM DEPTH OF 1/8 BEND IS NOT EXCEEDED.

REV.	DATE	BY	CITY OF VICTORVILLE - ENGINEERING DEPARTMENT	
1/23/67		PATTERSON	<b>SEWER CLEAN-OUT</b>	<b>SS-04</b>
1	3/22/93	D.G.H.		
2	7/25/07	STAFF		
			JOHN A. MCGLADE, CITY ENGINEER	SHEET 1 OF 1